


APPLICATION FOR ROAD CROSSING

Permission to lay within the County Right-of-Way may be granted if Exhibit "A" is attached with further restrictions.

The undersigned hereby requests permission to (bore or open) County Road _____

in _____ Township at the following location:

Note: Please show distance on sketch to nearest intersection



Type of work to be performed: _____

Type of road surface: _____

Note: See Item #2 of Conditions.

Depth of Pipe _____

*Depth of Cover _____

Road R/W Width _____

*Trench Width _____

(* Applies only if additional permission has been granted.)

Road Pavement Width _____

WE AGREE TO THE FOLLOWING CONDITIONS

1. To restore all disturbed surfaces to their original condition and adhere to the specifications or restrictions as outlined below.
2. All road crossings where said road is hard-surfaced (blacktop, concrete, chip and seal, etc.) will be made using the bore method unless further permission is granted from the governing authority regarding cutting the pavement.
3. To keep the disturbance to road surface and shoulders at a minimum, trenches within the road and shoulder areas will be backfilled with gravel and tamped, so that settlement of the material is minimized. If settlement does occur within one year of backfilling, additional suitable material will be put into place and compacted. The applicant shall make the necessary backfill with 304:02 stone and/or crusher run gravel as recommended by the County Engineer and maintain the same until the trench is firmly compacted. Whenever the backfill is so compacted the applicant shall notify the Morrow County Engineer for approval of the backfill. The applicant shall then resurface that portion of the road disturbed with material approved by the County Engineer.
4. Traffic will be maintained at all times, unless permission is granted by the governing authority to close the road. Any necessary lights, signs, barricades, and/or flagmen and watchmen will be placed on the job for the protection of traffic at all times, day and night, during the time this work is being done and that instructions given by the governing authority as to handling of traffic will be fully complied with. It is also agreed that the applicant will post signs and lights along said highway 500 feet distant each way from work site.
5. All mailboxes, signs, yards, driveways, drainage structures, fences, ditches, sidewalks, or other pertinent property damaged or removed during initial construction or future maintenance will be replaced or repaired as good as or better than existing.
6. To notify all property owners within the construction area at least ten (10) working days before work begins.
7. Any drainage tiles encountered will be repaired or replaced.
8. To assume the responsibility for and to save the governing authority, as signed below, harmless from any and all claims arising from the work performed, for personal injuries and property damages due to the direct sole negligence of the applicant, and to defend any action arising therefrom.

EXHIBIT 'A'

ATTACHMENT TO ROAD CROSSING PERMIT

The granting of this permit shall be subject to the following additional terms and conditions.

1. As shown on the sewer line plans dated _____ the length of boring for County Road Crossings shall be from R/W Line to R/W Line.
2. The _____ and service lines that cross the County right-of-way shall be a minimum depth of 48" below the existing ground line across the entire right-of-way.
3. No road cuts will be made or permitted on blacktop roads or gravel where there is a blacktop surface in front of the residence.
4. This permit is a permit to lay the sewer within County Right-of-Way.
5. The final location of the sewer line shall be determined under the authority of the County Engineer if any difference arises.
6. County Road closings shall be kept at a minimum. No County Roads shall be closed more than 3 hours unless permission has been granted by the County Engineer.
7. It shall be the sole responsibility of the permit applicant and the contractor to make sure all of the Emergency Squads, Fire Departments, Schools and Sheriff's Department are properly notified 2 days in advance of any road closings.
8. The Morrow County Commissioners shall be notified of any Township Road Closings. Permits for Township road crossings, etc. shall be issued by the Township Trustees of that township.
9. A copy of the current insurance policy and liability limits shall be furnished to the Morrow County Commissioners, prior to any construction.
10. A copy of the as built plans shall be furnished to the County Engineer upon completion of the project.
11. Markers identifying the owner, address, phone number, type, location and direction of the main pipeline, shall be on the Right-of-Way lines when installations are to be made within the County Right-of-Way.
12. The project inspector shall be approved by the County Engineer. If at any time the County Engineer does not feel the interests of Morrow County are being protected an inspector of our own choosing will be selected to inspect the project. The applicant shall be required to pay the inspector an hourly rate set by the County Engineer and payment will be made directly to the inspector.
13. If at any time in the future the _____ line is required by the County to be relocated for whatever reason, the cost of said relocation shall be borne entirely by the utility company or their successors.
14. It is strongly recommended and preferred that the utility acquire private easements outside the County right-of-way and locate the proposed sewer line on said easement.

9. If, in the future, improvements or relocations are made to any of the above portions of roads, it will be the financial responsibility of the applicant or successors to move or relocate such installations at the request of the governing authority.
10. To notify all utilities in the right-of-way ten (10) working days prior to construction by calling the Ohio Utilities Protection Service at 1-800-362-2764 for notification of members utilities. Non-members must be called directly.
11. To notify the governing authority at least ten (10) working days before construction.
12. The undersigned Governing Authority will not be held liable for damage to the Company's or Owner's facilities covered by this permit unless such damage is due to the negligence of the Governing Authority.
13. This permit is granted on the condition that the applicant agrees to hold the County of Morrow free from any and all damages that may arise through his negligence in the use of this permit.
14. It is the contractors and/or petitioners responsibility to strictly adhere to all current applicable OSHA standards, and any other state and/or Federal regulations. Morrow County assumes no liability to petitioner, contractor or any third parties involved with this permit.

Petitioner _____

Local contact, person in charge of work being performed.

Address _____

Name _____

Phone No. _____

Phone No. _____

Additional Remarks if Any: _____

Approved: County Engineer _____

Petition Granted By:

By _____

County Commissioner

Additional Restrictions or Comments: _____

County Commissioner

County Commissioner

Expiration Date of Permit for Construction:

Date _____